



After **SVI Refurb**



St. Helena Fire Department Tanker Refurb #1070R

Existing Chassis

Peterbilt

Before



Refurbishment Details

Waterous CLK 500 GPM Pump Installation

Whelen PSTank Level Lights Installation

Foam Pro 1600 Foam Unit with Tank Installation

New Graphics and Rear Chevron Installation

Rear Fan Type Spray Heads Addition

Upgraded Warning Lights to Whelen LED

OnScene Brand Stick Lighting Installations

Rebuilt Body Doors from Aluminum

Saint Helena (CA) Tanker

Complete Refurb Details

BODY

- Rebuild the body doors from aluminum, replace hinges and hardware
- Remove existing pump and panels
- Remove upper cross lays and make into a dunnage area
- Install a Waterous CLK 500 GPM pump with a new stainless manifold
- Install New stainless pump panels
- Add fan type spray heads to both sides of the truck on the rear
- Fabricate a slide tray for a pump in RF lower compartment for pump
- Mount the hard suction from its existing location onto the tank lift
- Clean up storage in the rear of the truck to make it more user-friendly
- Add area above the compartments for 200' of 3" supply hose
- Add Whelen PSTank level lights
- Add a back-up camera with a flip-down screen
- Add a FoamPro 1600 foam unit with a tank

GRAPHICS

- Add new graphics and rear chevron

LIGHTING

- Upgrade scene lights around the truck to 12-volt Whelen Pioneers
- Upgrade all compartment lights to OnScene Solutions brand stick lighting
- Upgrade warning lights to Whelen LED
- Upgrade tail and marker lights to LED